# BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.81

## APPROVED SCHEDULE - B

**Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012**

**Name of Work: IMPROVEMENTS OF ROADS AND DRAIN IN VAYANANDANA LAYOUT & NETHAJI NAGARA IN WARD NO. 07.KODIGEHALLI SUB DIVISION.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of C.SHIVARAJU | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 68.40 | Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 66.00 | Rupees Sixty Six Only |
| 2 | 410.40 | Removing BS Slab of drain and stacking. complete Complete as per Specification and Directions of Engineer in charge of the Work | Sqm | 50.00 | Rupees Fifty Only |
| 3 | 410.40 | Refixing stone slabs of drains and pointing in CM 1:3. complete Complete as per Specification and Directions of Engineer in charge of the Work | Sqm | 64.00 | Rupees Sixty Four Only |
| 4 | 358.00 | Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specification. complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 150.00 | Rupees One Hundred Fifty Only |
| 5 | 51.00 | Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 4100.00 | Rupees Four Thousand One Hundred Only |
| 6 | 54.00 | Providing and constructing granite size stone masornry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 3000.00 | Rupees Three Thousand Only |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore-560092

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of C.SHIVARAJU | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 7 | 90.00 | Providing flush pointing to square rubble, course or uncoursed stone masonry with CM 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete Complete as per Specification and Directions of Engineer in charge of the Work | Sqm | 84.00 | Rupees Eighty Four Only |
| 8 | 102.60 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete Complete as per Specification and Directions of Engineer in charge of the Work | Sqm | 340.00 | Rupees Three Hundred Forty Only |
| 9 | 9.60 | Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete Complete as per Specification and Directions of Engineer in charge of the Work | | 4560.00 | Rupees Four Thousand Five Hundred Sixty Only |
| 10 | 25.00 | Construction of embankment with approval material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 150.00 | Rupees One Hundred Fifty Only |
| 11 | 68.63 | Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC Works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3 with all lead and lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns Staircase and Roof with M-20 (1:1.5:3) (Cement 320kg/cum) complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 5200.00 | Rupees Five Thousand Two Hundred Only |
| 12 | 955.50 | Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete Complete as per Specification and Directions of Engineer in charge of the Work | Cum | 319.90 | Rupees Three Hundred Nineteen and Ninety Paise Only |

Executive Engineer
Byatarayanapura Division
Yalahanka [illegible] B.B.M.P.
Bangalore-560092

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of C.SHIVARAJU | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 13 | 38.92 | Providing TMT. Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design ( laps, hooks and wastage shall not be measured and paid) cost of materials, lobour, HOM of machinery complete Complete as per Specification and Directions of Engineer in charge of the Work | Qtl | 7500.00 | Rupees Seven Thousand Five Hundred Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092